ENGINEERING DEPARTMENT.

MYSORE HEADQUARTER RANGE.

Notification dated 13th December 1921.

Notice is hereby given that sealed tenders will be received at the Office of the Assistant Engineer, Headquarter Range, Mysore, up to 2nd October 1921, for constructing additional buildings to Krishnarajendra Hospital at Mysore. An approximate estimate of quantities is given below:— These quantities are not guaranteed. The work should be completed by the end of December 1922.

2. The plans, detailed estimate and conditions may be seen at the Assistant Engineer's Office at Ramavilas Agrahar, between the hours of 11 and 5 P.M., on any working days.

3. Tenders should be submitted on printed forms, which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees as detailed below in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing additional buildings to Krishnarajendra Hospital at Mysore" in default of which, tenders will be rejected.

5. Indefinite remarks such as 'as per data' 'as per market rate,' 'as per estimate' will not be considered. Only specific rates should be quoted. Rates quoted should be written in words and figures.

6. The contractors should bear the usual hire and depreciation charges on Government machinery lent to them.

7. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

8. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money forfeited.

9. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Assistant Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

10. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

11. Government materials supplied should be accepted by the contractor only fixing charges be paid on them.

		Rs.
(1)	Constructing covered passage	200
(2)	Do 2 Probationary Nurses' Quarters	275
(3)	Do 5 Sub-Assistant Surgeon's quarters ...	450
(4)	Improvements to Wards Nos. 4, 6, 7 and 8	100
(5)	Do to Resident Medical Officer's quarters ...	175

Abstract estimate of constructing connecting Corridor and Miscellaneous works in connection with the compound of the Sri Krishnarajendra Hospital at Mysore.

No.	Items of work	Per	Quantity
1	Earthwork excavating foundation and filling in foundation and basement ..	100 C. ft.	8,010
2	Stone jelly concrete in mortar	C. ft.	2,670
3	Burnt brick in chunam foundation and basement	„	5,874
4	Do superstructure..	„	1,478
5	Chunam plastering	Sq.	54·44
6	Whitewashing	„	54·44
7	Burnt brick in chunam coping	R. ft.	13·14
8	Teakwood pillars, 6′ x 5″ x 5″, with bases and capitals	each	292
9	Teakwood work, wrought and put up, with wood oiling	C. ft.	547·65
10	Roofing with 1st class Mangalore tiles over 2″ x 1′ teak reepers, nails, wood oiling, etc., complete.	Sq.	85·44
11	Ridging Mangalore tiles set in mortar	R. ft.	712
12	Ornamental eave board, 9″ wide, with painting	„	1,332
13	Flooring with Cuddappah slabs, 1½″ thick over 3″ concrete bed and cement pointing.	Sq.	39·16
14	Zinc sheet for Valleys	S. ft.	525
15	Teakwood planks for Valleys	„	525

446

Abstract statement showing quantity of works required to be done for improving the wards Nos. 4, 6, 7 and 8 in the compound of Sri Krishnarajendra Hospital at Mysore.

No.	Items of work	Per	Improving the wards and adding Hindustani closet	Adding a wing room as a closet and bath
1	Removing the existing Arcot tiled roof with flat tiles, reepers and stocking them.	Sq.	12·63	..
2	Removing the double collered couples from the roof	No.	24	..
3	Removing the wall plates (old)	R. ft.	87	..
4	Dismantling the existing Hindustani closet, Main building walls, wall-plates, including carting debris.	C. ft.	279	..
5	Burnt brick in mortar	,,	777	538
6	Fixing the old couples..	No.	24	..
7	Fixing the old wall plates	R. ft.	81	..
8	Removing the existing small old windows	No.	7	..
9	Fixing new teak wood windows with iron bars, ½" diameter, including fittings with one shutter (panelled) only.	S. ft.	128	..
10	Roofing with 1st class Mangalore Tiles bedded in mortar 2" x ¼" thick Teak reepers with nails, etc., complete with flat tiles—	Sq.	11·31	..
11	Ridge tiles set in Morter	R. ft.	44	..
12	Chunam borders	,,	52	..
13	Chunam plastering the top portion, newly raised	Sq.	12	..
14	Whitewashing, 2 coats	,,	15·22	3·21
15	Colour washing	,,	13·32	..
16	Wood oiling, 2 coats, after scraping old wood .. .	,,	15·00	..
17	Painting doors and windows (with chocolate painting)	,,	8·25	1·52
18	Removing the existing asphalte floor and carting	,,	5·10	..
19	Flooring with 1½" thick Cudappa slabs over 3" concrete bed and cement pointing.	,,	5·10	..
20	Lintel slabs over windows and ventilators (6", one line dressed) ..	S. ft.	75	25
21	Earthwork excavating foundation and filling foundation and basement.	100 C. ft.	..	270
22	Stone jelly concrete in Mortar	C. ft.	..	93
23	Plastering with chunam	Sq.	..	8·27
24	Teakwood battened doors with fittings as per Moryat's specifications..	S. ft.	..	58
25	Teakwood glazed ventilators	,,	..	6
26	Teakwood wall plates and common rafters	C. ft.	..	8·21
27	Roofing with 1st class Mangalore tiles over 2" x 1" thick reepers with nails and wood oiling, etc., complete—	Sq.	..	2·3
28	Teakwood Eave board, 9" wide, 1" thick, with painting	R. ft.	..	43
29	Clearing site, etc.	L. S.	..	L. S.
30	Flooring to latrine with 6" concrete and ½" cement plastering ..	Sq.	..	37

Abstract statement of work to be done to the Resident Medical Officers quarters and out houses in the compound of Sri Krishnarajendra Hospital at Mysore.

No.	Items of work	Per	Main building	Covered passage	Kitchen block	Bath room	Stables
			Qty.	Qty.	Qty.	Qty.	Qty.
1	Removing the existing pot tiled roof with flat tiles and reepers and carting.	Sq.	35·27	..	11·16	4·23	..
2	Roofing with 1st class Mangalore tiles over teak reepers, 2"x 1" with nails, wood oiling, etc., complete	,,	35·27	2·70	11·16	4·23	9·35
3	Removing roof timber and re-fixing with fresh nails ..	,,	35·27	..	..	..	..
4	Ridging Mangalore tiles set in mortar	R. ft.	158	23	62	24	45
5	Burnt brick in mortar super structure	C. ft.	1,836	105	..	..	802
6	Chunam plastering	Sq.	35·88	0·40	..	..	14·01
7	Teakwood work, wrought and put up with wood oiling	C. ft.	78	25·20	10	..	48·30
8	Fixing new rectangular ventilators with glazed shutters.	S. ft.	77	..	..	..	..
9	Fixing zinc sheets for valleys, 3' wide	,,	312	..	..	..	..
10	Planking below zinc sheets, 1" plank	,,	312	..	..	..	..
11	Flooring with Mangalore square tiles over mortar bed and cement pointing.	Sq.	7·96	..	..	..	..
12	Removing existing floor	,,	7·96	..	..	..	..
13	Whitewashing 2 coats	,,	79·11	..	..	..	..
14	Distemper calcarium wash	,,	19·78	..	..	..	..
15	Wood oiling to roof timbers, 2 coats	L. S.	..	..	..	..	..
16	Chocolate painting, 2 coats	Sq.	10 16	..	..	..	..
17	Chunam borders	R, ft.	324	24	36	36	42
18	Burnt stone, slabs 6" thick, one line dressed ..	S. ft.	32	45	..	..	20
19	Earthwork excavating foundation and filling in foundation and basement.	100 C. ft	..	1·20	..	..	2·36
20	Stone, jelly concrete in mortar	C. ft.	..	60	..	..	93
21	Flooring with 1½" Cuddappa slabs over 3" concrete bed and cement pointing.	Sq.	..	1·00	..	..	..
22	Drainage	..	..	L. S.	..	..	..
23	Teakwood battened doors with fittings as per Maryat's specifications	S. ft	..	..	..	..	19
24	Cutting holes in stone posts	each	..	..	..	..	4

K. V. KARVE,
Asst. Engineer.

Abstract statement showing quantity of works required to be done for constructing compound wall in the compound of Sri Krishnarajendra Hospital at Mysore.

No.	Items of work	Per	Quantity
1	Earthwork excavating foundation and filling in foundation and basement ..	100 C. ft.	1,209
2	Stone jelly concrete in mortar	C. ft.	605
3	Burnt brick in mortar for foundation	„	680
4	Do superstructure	„	874
5	Coping with burnt brick in mortar	R. ft.	403
6	Chunam plastering	Sq.	26·23
7	Storm water drain	L. S.	
8	Fixing a wooden wicket gate	L. S.	

Abstract statement showing quantity of work required to be done for Sub-Assistant Surgeon's quarters and Probationary nurse's quarters in the compound of Sri Krishnarajendra Hospital at Mysore.

No.	Items of work		Plan A Sub-Assistant Surgeon's quarters	Plan B Sub-Assistant Surgeon's quarters	Probationary Nurse's quarters
			Quantity	Quantity	Quantity
1	Earthwork excavating foundation and filling in foundation and basement.	100 C. ft.	19·44	1,890	2,484
2	Stone jelly concrete in mortar	C. ft.	626	603	667
3	Burnt brick in mortar foundation and basement ..	„	1,952	1,901	1,840
4	Do superstructure	„	2,296	2,233	2,784
5	Burnt brick in mortar arch work	„	4	..	40
6	Burnt stone slabs, 6" thick, one line dressed	S. ft.	231	199	177
7	Teakwood panelled doors, 1¼ with fittings, complete as per Maryat's specifications.	„	249	214	223
8	Teakwood battened doors with fittings as per Maryat's specifications.	„	18	..	..
9	Teakwood panelled windows with round iron bars ½" and fittings complete only one shutter outside as per Maryat's specifications.	„	235	153	72
10	Teakwood circular ventilators with fittings	„	9	..	..
11	Teakwood work wrought and put up including wood oiling ..	C. ft.	118·62	107·11	87·58
12	Roofing with first class Mangalore tiles over teak reepers 2" x 1" with nails, wood, oiling, etc., complete.	Sq.	16·24	16·05	15·19
13	Ridging Mangalore tiles set in mortar	R. ft.	170	126	66
14	Zinc sheets for valleys	S. ft.	214	392	144
15	Teakwood planks below valley, 1" thick	„	214	392	..
16	Plastering with chunam	Sq.	66·72	65·40	53·58
17	White and colourwashing	„	66·72	65·40	53·58
18	Teakwood eave board, 9" wide with painting (ornamental)	R. ft.	200	242	220
19	Barge board, 2' wide with painting (teakwood) do ..	Sq.	78	166	88
20	Window hoods (teakwood)	„	32	32	..
21	Ornamental parapet wall over compound wall including moulding, etc., 3' high.	R. ft.	51	..	..
22	Chocolate painting to doors and windows	Sq.	15·92	8·87	12·05
23	Flooring with 1½" Cudappah slabs over 3" concrete bed and cement pointing.	„	3·51	5·03	6·76
24	Flooring with Mangalore 9" x 9" square tiles over 3" concrete bed and cement pointing.	„	4·89	3·70	..
25	Teakwood railing, 2½' high	R. ft.	32·50	37	..
26	Teakwood finials with painting	No.	4	6	4
27	Earth forming, levelling, draining, etc.	„	L. S.	..	..
28	Teakwood pedents	„	16	22	..
29	Couping with brick in mortar over compound wall ..	R. ft.	..	50	..
30	Constructing sink in the bath, seats in latrine and ornamental plaster work, etc.	..	..	L. S.	..
31	Teakwood pillars with bases and capitals	No.	..	..	4
32	Teakwood gothic head over windows with glazed shutters revolving arrangements.	S. ft.	..	..	20
32	Teakwood ventilators with glazed shutters	„	..	..	27
34	Chunam borders	R. ft.	..	..	112
35	Plinth drain alround the basement	..	..	..	L. S.
36	Constructing fire place, etc.	..	..	..	L. S.